



**PRE BID
ADDENDUM NO. 3**

TO THE BID DOCUMENTS

FOR

CONEJO VALLEY UNIFIED SCHOOL DISTRICT

AT

Newbury Park High School
Softball Field and Parking Lot

PROJECT # MP19/20-16-NPH

PREPARED BY

Name – Ken Thomas

July 16, 2020

NOTICE TO BIDDERS: You are hereby notified of the following changes, clarifications or modifications to the original Contract Documents, Project Manual, Drawings, Specifications and subsequent Addenda. This addendum shall supersede the original contract documents, and any previous addenda wherein it contradicts the same and shall take precedence over anything to the contrary therein. All other conditions remain unchanged. The bidders shall acknowledge receipt of this Addendum in the Bid Form, Specification Section 00 21 00.

This Addendum consists of 3 pages:

ADDENDUM NO. 3

Project # MP19/20-16 NPH
Page - 1 OF 3

Changes to the Project Plans/Specifications:

<u>ITEM</u>	<u>SHEET/SECTION</u>	<u>DESCRIPTION</u>
1.	Sheet L1.00	- Add the following: Provide and install isolation valves @ ALL QC's on drawings.
2.	Sheet L1.00	- (3) 3/4" RCV's shown, Revise to 1" (EC-1, EC-2 and EC-3)
3.	Sheet E1.0	- Add 1-1/4" conduit to backstop for Irrigation Controller provide 15A circuit with GFCI
4.	Sheet E1.0	- Add courtesy outlets (1 each) @ both dugouts. (3/4" conduit on same circuit)
5.	Sheet E1.0	- Ref Note #4 Revise Reference Note #4 to read: Scoreboard IS NOT part of this contract.
6.	Sheet E1.0	- Ref Note #5 Add the following: See Sheet A1.01 Ref Note #9 for new location of relocated scoreboard.
7.	Sheet A1.00	- Note #20 Revise to read: 16' wide sliding maintenance gate.
8.	Sheet A1.02	- Note #4 Revise note #4 to read: Provide 8' tall C/L fencing per Detail #24 on S8.0.
9.	Sheet A1.02	- Note #16 Revise to read: Provide 8' tall C/L fencing per Detail #24 on S8.0.
10.	Sheet A1.02	- Note #17 Remove this note in its entirety.
11.	Sheet A1.02	- Note #18 Revise to read: New 8' height C/L fencing at existing baseball field will be located inward towards home plate approximately 10' @ center field to accommodate new "Batters Eye". Corners @ 1 st and 3 rd base sides will remain the same distance as existing.
12.	Sheet A1.02	- Note #30 Revise to read: 16' wide x 6' high sliding maintenance gate.
13.	Sheet A1.02	- Note #22 ADD to read: (Installed by others)
14.	Sheet A10.00	- Detail #14 shows 4 1/2" posts at 10'o.c. Revise to: "2 1/2" posts at 8'o.c."
15.	Grading Contractor	is to remove existing 20'+/- flag pole. Save pole to re-installed by Concrete Contractor
16.	Concrete Contractor	to re-install Flag Pole at location TBD. Include in scope of work.

ADDENDUM NO. 3

- 17. **General** - Outfield fence guard to be installed on outfield fences only.
- 18. ADD Alternate Bid Item: # 1 - Steel Shade Cover as shown on Sheet A2.02, A5.02, S4.0, S5.0 and related sheets throughout the Bid Set.
- 19. ADD Alternate Bid Item: # 1 – Concrete footings for Shade Structure Cover on A2.02, A5.02, S4.0, S5.0 and related sheets throughout the Bid Set

Please acknowledge receipt of this **Addendum No. 3** by return e-mail to:

Mike Stanford – mikestanford@conejouisd.org

Acknowledge this and all Addenda with your bid package on the Bid Form.

ADDENDUM NO. 3 TO THE BID DOCUMENTS FOR Softball and Parking Lot Project MP19/20-16-NPH	
<u>ACKNOWLEDGEMENT:</u>	
_____	_____
Signature	Date
_____	_____
Name (Print or Type)	Company Name

ADDENDUM NO. 3